




Small New Build Project: Long Four Acres

Martin Ingham





# LOCATION PLAN SCALE 1:1250

## SITE PLAN




# Design:

- Meet our needs
- Comply with Design Code
- Energy Efficient
- Employ natural materials
- Quick to build
- Proven approach

Passivhaus Plus targeted  
Parsons+Whittlely architects for planning,  
Void Architecture for building control  
MBC Timber Frame  
WARM certifiers



Simple box form  
 +ASHP  
 +MVHR  
 +PV panels & battery  
 Cost conscious  
 no EV yet



# ARCHITECTURAL DESIGN & AESTHETICS: Section & images



# The Build


Started on site Nov. 2019

Foundations, Frame, Windows, Zinc,  
Air-tightness works, Penetrations and  
insulation blown

Then... COVID

Singular trades  
Self project managed  
Supervision difficult  
Supply & labour issues

Occupied Dec 2020



# Airtightness

MBC works

March 2020 0.47 ach

Penetrations & cellulose blown

June 2020 0.77 ach

Actions:

- additional taping
- sub-contractors guided on maintaining air-tightness
- Covid restrictions compromised regular oversight

March 2021 0.81 ach

Certification on hold



# Monitoring


10+ years Wimbish experience

Budget limits


App. Sources

Fine granularity


## Tinytag Loggers




## MELCloud Data




## Tesla App



## Octopus Data



## Nearby Weather Station



# Energy


	Demand	Generation
<b>PHPP</b>	<b>&gt;22.5*</b>	<b>30.4</b>
2021	27.6#	29.9
2022	26.7	31.4
2023	26.9	28.6
2024	25.1	27.3

Chart excludes battery losses

\* data incomplete, figure a little low

# early heating issues

Positive balance possible because  
Passivhaus construction  
means that demand is low



**Energy demand** kWh/(m<sup>2</sup>·a) based on 230m<sup>2</sup> GIA



# Electricity


In 4.5 years:

We've paid £226,  
Gov't £600,  
Balance > £343

Over 2024 our balance fell  
£15/month

Tariff significant

Heating < £80 pa.





# Comfort: Temperature

comfortable throughout.

very rarely below 19°C

Infrequent overheating (>25°C)  
2.3% in 2024.



PERFORMANCE & FEEDBACK: comfort



# Summer comfort:

% Overheating/year:  
2.2% (from PHPP v9.6)

## Design:


- High levels of insulation.
- Triple-glazed windows.
- Overhangs.
- MVHR: which automatically enters bypass mode and 'coolth' recovery.
- Internal blinds and curtains.
- External temporary sails & parasol.



# Summer comfort in practice:


## Interventions:

- Window opening fine: quiet rural location
- “Cool evening” forecast:
  - reduce the heat gains
  - When cooler outside throw open windows.
- “Hot evening” forecast:
  - take all possible measures to limit heat gains. close windows, blinds and curtains, put up the sail, and minimise warming activities.
  - Our home will then remain cool
  - Purge ventilate when possible.



# July 22 Record Temperatures

- Hot evenings were expected on 18<sup>th</sup> and 19<sup>th</sup>.
- Sought to keep the heat out.
- Outside 38°C Inside 28°C.
- Late eve before cooler outside than in.
- Bedroom temperatures remained uncomfortably warm but given record temps...




# Comfort: Humidity

Comfortable throughout.

2024 dining room was mostly between 37% and 56% RH.

Summer higher when windows open  
Winter lower.

Adding house plants.



# Comfort: air quality


Ventilation system:

- Designed by Alan Clarke
- Supplied and commissioned by 21°(GBS)
- Regular inspection, cleaning and replacement of the filters and cleaning of terminals, attenuators and fans.



# Costs:

- £2,374 /m<sup>2</sup> GIA
- More than we had budgeted
- PH element: Insulation, windows etc. a factor
- Covid cost us extra – rates, prices, delays
- Choices of internal and external finishes, fixtures and fittings
- PV and battery



# Embodied carbon:

- Aspiration: use natural materials:
  - timber frame, cellulose insulation
  - avoid structural steel
- Material choices:
  - Aluminium and Zinc: poor upfront but reclaimable. Longevity and low maintenance.
  - ASHP: no low GWP devices available.
  - Ash staircase and bamboo flooring (no fitted carpets)
- Post-build calculation unreliable:
  - EPDs for elements such as the ASHP were not available
  - where our SunPower PV panels had been made.
  - Approach inherently low carbon.
  - Other MBC build and research with Lincoln University low values.



# Industry & Community Impacts

- We delivered the build in good time
  - through a pandemic
  - subsequent builds would be easier
- Most elements were straightforward.
- delivering an 'almost Passivhaus' can be done
- An exemplar for the local community.
- Visits - 4 couples have taken inspiration for their own builds
- building and living in the property, has taught many lessons applied on other timber frame projects.
- share the outcomes of the project
  - on LinkedIn
  - these Awards.


# Applicability at scale

- The off-site timber frame
  - low carbon construction
  - Energy efficient
  - at pace
  - should be used at scale.
- the design could easily
  - become semi-detached houses
  - with a little more modification, a terrace.



# Do differently

- Greater attention to embodied carbon
- Review options for heating and hot water
  - ASHP is costly for how little it is used
- Slightly smaller windows
- More modest.
- Consider a different roof shape, largely for the PV:
  - Planning requirement;
    - little impact on annual PV output,
    - more significant in winter
  - Access for cleaning is difficult
- More PV



# Rear garden early morning



Notes:

- Nature friendly
- Native hedging
- Retained grass
- Poles for sails & washing line

Conclusion

